Bhagat Phool Singh Mahila Vishwavidyalaya
Department of Engineering Cell
Khanpur Kalan (Sonepat), Haryana-131305

Office No. 01263-283007,283530, Fax No. 01263-283779, www.bpswomenuniversity.ac.in

NOTICE Re-INVITING TENDER

Sealed tenders as per schedule/DNIT attached are hereby Re-invited on behalf of Registrar in her Office at BPSMV Khanpur Kalan through Registered post/speed post from Eligible Contractors, L&C Societies and from the firm of similar nature of work etc. If the date on which the tenders are to be received is declared holiday then the tender will be received on the next working day. The tender shall be opened on the same day in the presence of the tenderer or the authorized representative/agents who may like to be present at that time:-

Sr. No.	Name of Work	App. Cost.	EMD to be deposited by Contractor/firm L&C Society (Rs. In thousands)	Time Limit	Date & Time for Receiving of Tender		Date & Time for opening of Tender	
					Date	Time	Date	Time
1.	Tender for repair of false ceiling of New Academic Block building of Regional Centre, Kharal (Re-Tender)	97,000/-	1900/- for contractor& 950/- for L&C Society	**21 Days**	**08.12.26**	**1:00 pm**	**08.12.26**	**11:00 am**

1. The rates of all items should be quoted on item rate basis.
2. The limited tenders/quotations may be sent in favour of Registrar, BPSMV Khanpur Kalan, in sealed envelope through Registered Post/Speed Post with mentioning tender name in bold letter on the envelop.
3. The EMD will be deposit in the form of D.D. in the favour of Registrar, BPSMV, Khanpur Kalan.
4. Engineering –In-Charge is competent to increase/decrease the quantity of work.
5. Central/ State taxes will be deducted as applicable from time to time.
6. The work shall be carried out as per specifications given in DNIT.
7. No extra payment will be paid to you.
8. The work will be completed within prescribed time.

SDE (Civil)
For Registrar

Endst. No./ BPSMV /Engg./26/ Dated

A copy of the above is forwarded to the following for information and necessary action:-

1. Notice Board.

SDE (Civil)

DETAILED NOMINCLATURE.

NAME OF WORK: -Tender for repair of false ceiling of New Academic Block building of Regional Centre, Kharal

Approx. Cost : Rs. 97000/-

Date of Tender: 08.12.2026

Sr. No.	Description of items	Qty.	Unit	Rate to be quoted by the agency in words and in figures, FOR including VAT & taxes.	
				In Figure	In Word
1.	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets andgalvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS: 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x1 Ox0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre, with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the	**274.06**	**Sqm.**		

	help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering up to 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charae but excluding the cost of oaintina with 9.46.1 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) (HSR- 9.46.1)				
2.	Providing and fixing false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (both side inclusive) as per IS: 277 and consisting of angle cleats of size 25 mm wide x 1.6 mm thick with flanges of 27 mm and 37mm, at 1200 mm centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm long with 6mm dia bolts, other flange of cleat fixed to the angle hangers of 25x1 Ox0.50 mm of required length with nuts & bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm running at the spacing of 1200 mm centre to centre, to which the ceiling section 0.5 mm thick bottom wedge of 80 mm with tapered flanges of 26 mm each having lips of 10.5 mm, at 450 mm centre to centre, shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm long G.I. wire at every junction, including fixing perimeter channels 0.5 mm thick 27 mm high having flanges of 20 mm and 30 mm long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm centre,	25	Sqm.		

	with 25mm long dry wall screws @ 230 mm interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering up to 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cut outs made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charae but excluding the cost of oaintina with 9.46.1 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) :2011 (Board with BIS certification marks) (HSR- 9.46.1)				

JE (Civil)